

ITALY – LOADOUT AND WEIGHING ACTIVITIES OF JACKET AND DECK MODULES

PROJECT	EQUIPMENT	WEIGHT
OFFSHORE	SPMTs	UP TO 3,728 TON

Italy: Fagioli Spa were involved in the weighing, transport and load out operations of jacket and deck modules. SPMTs were used for the overall activities which involved also the engineering department for the risk assessment documentation and calculation reports.

Picture on the right shows the load out of a 3728 ton jacket module, 112 mts long, by means of 188 axle lines SPMTs and 8 PPUs. The trailers were previously employed for the weighing operation. Fagioli performed also the transport and load out of a deck module weighing 2729 ton, 62 mts long which was moved by 122 axle lines SPMTs. After this operation Fagioli also executed the load out activity of a 780 ton deck module.

